Take up, remove bed and backing, pallet stack and deliver Yorkstone setts from Lay-by to client's store. Bedding mortar to be tipped off site. Base layer to be planed out to depth of main carriageway excavation (66.43m^2)

Granite kerbs to be retained (5.75m and 5.66m)

Take up, remove bed and backing and set aside Granite dropped kerbs for re-use (6.1m)

Existing Kerb to be retained

Take up, remove bed and backing and set aside Granite dropped kerbs for re-use (5.83m)

Take up and set aside Yorkstone setts and slabs from access area (29.19m^2)

Take up, remove bed and backing, pallet stack and deliver Granite setts from channel to client store. Bedding mortar to be tipped off site. Base layer to be planed out to depth of main carriageway excavation

Granite kerbs to be retained (6.5m and 6.2m)

Take up, remove bed and backing and set aside Granite dropped kerbs for re-use (6.0m)

Take up, remove bed and backing, pallet stack and deliver Yorkstone setts from Lay-by to client's store. Bedding mortar to be tipped off site. Base layer to be planed out to depth of main carriageway excavation (84.02m^2)

Take up, remove bed and backing and set aside Granite dropped kerbs for re-use (11.8m & 6.1m)

Take up, remove bed and backing, pallet stack and deliver Yorkstone setts from Access areas to client's store (35.78m^2 & 24.16m^2)

Existing Kerb to be retained

Take up, remove bed and backing, pallet stack and deliver Granite setts from channel to client store. Bedding mortar to be tipped off site. Base layer to be planed out to depth of main carriageway excavation

Take up, remove bed and backing and set aside Granite dropped kerbs for re-use (6.0m)

Granite kerbs to be retained (6.00m and 6.00m)

Nursery

Lindpet House

PH

MARKET PLACE

Bank

Westgate Hall

TAXIS

LEGENDS:

- EXISTING KERBS TO BE RETAINED
- EXISTING GRANITE DROPPED KERBS TO BE RAISED TO FINISHED LEVEL. REMOVE BED AND BACKING, CLEANED FOR REUSE
- EXISTING TARMAC CARRIAGEWAY TO BE PLANED OUT TO A DEPTH OF 330mm FROM EXISTING CARRIAGEWAY LEVEL (621.21m^2)
- TAKE UP AND SET ASIDE EXISTING GRANITE 100 X100 CHANNEL SETTS. REMOVE BED AND BACKING, PALLET STACK AND DELIVER TO CLIENT STORE. (43.85m^2)
- TAKE UP AND SET ASIDE YORKSTONE SETTS, REMOVE BED AND BACKING, PALLET STACK AND DELIVER TO CLIENT STORE (150.44m^2)
- TAKE UP AND SET ASIDE YORKSTONE SETTS AND SLABS, REMOVE BED AND BACKING, PALLET STACK AND DELIVER TO CLIENT STORE. PLANE OUT 270mm, (89.13m^2)
- EXISTING ROAD GULLY GRATES AND FRAMES TO BE TAKEN UP, CLEANED AND RETAINED FOR RE-USE, SEE DRAWING NO. 0843/02/2003 FOR DETAILS
- EXISTING IRONWORKS TO BE RAISED, SEE DRAWING NO. 0843/02/2003 FOR DETAILS RELATING TO REUSE OR REMOVED AND TIPPED OFF SITE



Location Plan
Scale 1:50,000

NOTES:

1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
2. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT DOCUMENTATION, DRAWINGS AND STANDARD DETAILS.
3. DO NOT SCALE FROM THIS DRAWING.
4. CONFLICTING INFORMATION SHOWN ON THE ENGINEER'S DRAWINGS OR DISCREPANCIES BETWEEN THE INFORMATION GIVEN BY THE ENGINEER AND THAT PROVIDED BY OTHERS MUST BE REFERRED TO THE ENGINEER BEFORE THE WORKS COMMENCE.
5. EXISTING FOOTPATH PAVING AND STREET FURNITURE IS TO BE RETAINED.
6. EXISTING KERBING TO REMAIN UNLESS OTHERWISE STATED.
7. CLIENT STORE IS BARROWBY DEPOT.
8. FOR ROAD MARKINGS, REFER TO DRAWING 0843_02_4000 - CARRIAGEWAY MARKINGS.

Suitable for Tender

FOR THIRD PARTY USE THIS DRAWING SHALL BE DEEMED CURRENT ONLY AT THE DATE OF APPROVAL - PLEASE CHECK FOR AMENDMENTS BEFORE USE

Revision	Date	Description	Drawn By	Eng Chck By	Dev Chck By	Approved By
C01	14/12/23	First Revision	MG	SR	JT	JT

Amendment Details

Drawn by	Checked by	Approved by
M.Gissing Date 15/01/24	S.Rehman Date 15/01/24	J.Thomas Date 15/01/24

Road No	Site Ref: N/A
Parish: GRANTHAM	SCN No: N/A
Scale: 1:200 (Do not scale from this drawing)	Original Size: A1 / Structure No: N/A

Description

GRANTHAM FUTURE HIGH STREET
SITE 02 - MARKET PLACE
SITE CLEARANCE

Drawing Reference Number

0843-LCC-RDS-SK-02-DE-RDS-02000

Purpose	Revision	Suitability
Suitable for Tender	C01	S4

TSP, Highways
County Offices
Newland
Lincoln LN1 1YL
Customer Service Centre : (01522) 782070

Lincolnshire COUNTY COUNCIL
Working for a better future

LINCOLNSHIRE COUNTY COUNCIL - Reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. OS Licence 100025370